

Additional Earthquake repairs to Elmdale Lane – Unit 3

Extent of work:

- Epoxy injection concrete floor crack repairs – 6.2 lineal metres
- Banding of floor expansion joints – 6 lineal metres

Additional Earthquake repairs to Elmdale Lane – Unit 5

- Epoxy injection concrete floor crack repairs – 19.5 lineal metres
- Epoxy injection concrete wall crack repairs – 2.0 lineal metres
- Banding of floor expansion joints – 4.0 lineal metres

Additional Earthquake repairs to Elmdale Lane – Unit 7

- Epoxy injection concrete floor crack repairs – 23.3 lineal metres
- Banding of floor expansion joints – 17.2 lineal metres
- Floor leveling, uplift existing carpet & lay new carpet to office 1 & rear workshop due to damage from liquefaction – 31 m2
- Interior repainting – 19 m2

Additional Earthquake repairs to Elmdale Lane – Unit 9

- Epoxy injection concrete floor crack repairs – 16.2 lineal metres
- Epoxy injection concrete wall crack repairs – 5 lineal metres
- Banding of floor expansion joints – 15.65 lineal metres
- Floor leveling, uplift existing carpet & lay new carpet to showroom/hallway due to damage from liquefaction – 64 m2
- Exterior repainting – 75 m2

Additional Earthquake repairs to Elmdale Lane – Unit 11

- Epoxy injection concrete floor crack repairs – 10.5 lineal metres
- Epoxy injection concrete wall crack repairs – 2.3 lineal metres



Unit 7 additional wall repairs.



Unit 7 floor banding and liquefaction to existing carpet.



Unit 9 additional floor repairs.



Unit 9 additional wall repairs.